



Velox mobile plants have the capacity from 60 m³/hr up to 120 m³/hr. As the contractor companies needs to move their plants frequently, mobile plants are the ones which supply concrete where ever they needed to. Whenever there is a space limitations, mobility and fast set up are concerned. Velox mobile plants are the optimal solution with high European standarts.

### **Fully Mobile**

As it is fully mobile, all the components are on one platform which is ready to be moved by one truck. (Aggregate bins, cement, water, additive bins etc.).

## **Durable and Heavy**

Durable and heavy main chasis lets the plant for long operation life and safe transportation.

## **No Foundation Required**

# Assembly / Disassembly Easiness

## Wet and Dry

The availability for the systems for wet and dry production with 2 mixers. Both with skip hoist and transfer belt systems according to your demands.

#### **Technical Details**

Model	XM-60	XM-100	XM-120	XM-120 d
Compacted Concrete Output	60 m3/h	100 m3/h	120 m3/h	120 m3/h
Total Motor Power Rating	90 kW	155 kW	175 kW	190 kW
Mixer Type	Single/Twinshaft/ Planetary	Twin Shaft	Twin Shaft	Twin Shaft
Mixer Capacity	1500 It	3000 lt	4500 It	4500 It
Compacted Concrete Capacity	1000 It	2000 It	3000 It	3000 It
Mixer Motor Rating	37 kW	2x37 kW	2x55 kW	2x55 kW
Agregate Bin Capacity	4 x 10 m³	4 x 15 m³	4 x 20 m³	4x30 m³
Aggregate Weighing Belt				1000x14500 mm
Aggregate Weighing Belt Motor Reating				15 kW
Agrega Transfer Belt Motor rating	15 kW	22 kW	22 kW	22 kW
Aggregate Transfer Belt Dimention	800x10500 mm	1000x11000 mm	1000x11000 mm	1000x13000 mm
Cement Weighing Bin	500 kg	1000 kg	1500 kg	1500 kg
Additive Weighing Bin	20 It	40 It	40 It	40 It
Water Weighing Bin	250 It	650 It	900 It	900 It
Additive Pump	0.75 kW	0.75 kW	0.75 kW	0.75 kW
Screw Conveyor	219 mm	273 mm	273 mm	273 mm
Weight	24000 kg	28000 kg	32000 kg	52000 kg